

## **TekA Step Extra Heavy Duty Mobile Safety Steps** **500kg Capacity**

The TekA Step Industrial Extra Heavy Duty Warehouse Ladders are fully welded using sturdy 25mm steel tube and are finished in a painted finish making these steps both robust and attractive. The TekA Step mobile safety steps are Extra Heavy Duty and manufactured from heavy duty steel tube & components, these warehouse steps are sturdy and super stable, giving the user that extra confidence and peace of mind when working at height. The Steel Safety steps have a certified massive safe working load capacity of 500 Kg. A choice of 2 colours are available.

With a range of platform heights and number of treads from 3 to 19, the TekA Step Heavy Duty Mobile Safety Steps are the perfect solution for all construction, retail, commercial, office, warehouse and industrial applications.

A wide range of optional extras to match the warehouse steps with your requirements are available from the drop down boxes such as extra deep platforms, platform gates, bars and L&R chains. We recommend you add at least a 200mm platform extension when ordering any platform gate, bar or chain.

**\*\*We can offer a platform height modification if you require a size that is not available as standard on the dropdown list. Please use the dropdown to select the size slightly over your required size (eg. required size 2100mm choose 2286mm) and add the Platform Height Modification from Optional Extras dropdown then quote the size you require in the notes section on the payment page.**

Standard Platform Size W x D: 559x400mm

All TekA Steps Are UK Manufactured.



## **TekA Step Extra Heavy Duty Mobile Safety Specifications**

| Code    | Platform Height mm | Overall Dimensions (HxWxD) mm | No of Treads |
|---------|--------------------|-------------------------------|--------------|
| TS3530  | 762                | 1712 x 762 x 850              | 3            |
| TS3540  | 1016               | 1966 x 762 x 1000             | 4            |
| TS3550  | 1270               | 2220 x 787 x 1180             | 5            |
| TS3560  | 1524               | 2474 x 813 x 1300             | 6            |
| TS3570  | 1778               | 2728 x 864 x 1500             | 7            |
| TS3580  | 2032               | 2982 x 889 x 1650             | 8            |
| TS3590  | 2286               | 3236 x 914 x 1850             | 9            |
| TS35100 | 2540               | 3490 x 991 x 2050             | 10           |
| TS35110 | 2794               | 3744 x 1067 x 2150            | 11           |
| TS35120 | 3048               | 3998 x 1143 x 2350            | 12           |
| TS35130 | 3302               | 4252 x 1219 x 2500            | 13           |
| TS35140 | 3556               | 4506 x 1245 x 2650            | 14           |
| TS35150 | 3810               | 4760 x 1270 x 2800            | 15           |
| TS35160 | 4064               | 5014 x 1295 x 3000            | 16           |
| TS35170 | 4318               | 5268 x 1320 x 3200            | 17           |
| TS35180 | 4572               | 5522 x 1345 x 3400            | 18           |
| TS35190 | 4826               | 5776 x 1440 x 3600            | 19           |

All Welded steel construction

Punched metal treads

Handrails either side of steps and 950mm over platform

Kick plate as standard on 7 treads and over

Hand lever locking bar to mobilise unit

Rubber tyred wheels and nylon castors

Rubber covered feet

Step width 559mm

Step rise: 250mm

Standard Platform Size (without options) W x D: 559x400mm

Certified Load capacity: 500kg

**Please Note:** All Dimensions are approximate and shown in mm



# PEGASUS MECHANICAL LIFTING

46 The Warren, East Goscote, Leicestershire, LE7 3XA

Tel: 0116 2537411 Fax: 0116 2539751

email: sales@pegasuslifting.co.uk web: www.pegasuslifting.co.uk



## LOAD TEST REPORT

This report does not authorise the equipment to be put into service. An EC Declaration of Thorough Examination May Be Required

|                       |            |
|-----------------------|------------|
| Report Number         | 50279      |
| Job Number            | --         |
| Customer Order Number | --         |
| Next Test Date        | 16/09/2026 |

|                    |             |
|--------------------|-------------|
| Report Prepared by | Mark Cluley |
| Date of Report     | 16/01/2025  |

|                     |
|---------------------|
| Customer            |
| INDUSTRIAL PRODUCTS |

|                                                                                          |
|------------------------------------------------------------------------------------------|
| Test Location                                                                            |
| Pegasus Mechanical Lifting<br>46 The Warren<br>East Goscote<br>Leicestershire<br>LE7 3XA |

### Test Details

| ID No.                         | DESCRIPTION OF ITEM | QTY | SWL   | PROOF LOAD |
|--------------------------------|---------------------|-----|-------|------------|
| TS<br>35-44-45-58-38 -<br>TSTD | STEPS               | 1   | 500KG | 500KG      |

### Description Of The Tests Applied

500KG PROOF LOAD APPLIED USING 20KG HAND WEIGHTS

### Results Of The Test Identifying Any Defect

TESTS COMPLETED SATISFACTORY WITH NO DEFECTS RECORDED.

Witnessed by Company Approved  
and Qualified Examiner

Mark Cluley

Authenticated by

S Platts